



ESTD.1932

INDIAN GYMKHANA

Tender Number : IG/PD/2023/005

Date : 24th May., 2023

Inviting sealed quotations for the below supply of material and installations. Last day for quotations being 4th June, 2023
For any clarifications or site visit you could contact 9880290924

Staff quarters - PUF Sheet/Panel Installation on existing Roof					
ITEMS					
Sl.No.	Description	Unit	Quantity	Rate (Rs)	Amount(Rs)
1	Providing and Fixing of Top Roof 30mm Puff Insulated sandwich Panel/Sheets of approved make	SqFt	1610.00		
	Specifications - PUF insulated sandwich panels for roof matching the existing roof Having top profile sheet with 28-30mm crust hight at 195-200mm pitch, inner liner tray and PUF Insulation between not less than 30 mm thick and width 1.0 mt. Panel shall have 0.50mm thick precoated GI sheet on both side of polyurethane foam confirming to IS 12436:1988 with standard profile with tongue & groove arrangement . The Precoated sheet shall be of minimum 240 mpa steel grade confirming to IS 14246:1995 and shall have zinc coating of minimum 120 gsm as per IS:277:1992, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20 micron. The PPGI sheet shall have plastic protective guard film of minimum 25 microns to avoid scratches while transportation. The PU foam shall be self-extinguishing, fire retardant type having minimum density of 40 Kg/cum(+,-2 Kgs) including CFC Free pannel should be GRIHA Certified. The panels shall be fixed to the steel frame structure with minimum 5 mm thick self tapping GI screws with EPDM seal of required length and nos. with minimum spacing of 300 mm c/c assembly/ the cost shall include ridge, soffit junctions & flashings as specified puff panel makers.				
2	Labour Charges, Hardware & necessary support/s for the above using 2 x 4 M.S Pipe 14guage with required slope	SqFt	1610.00		

Note

- GST to be quoted separately
- Power (Generator), Water Provided by Client on Site (Free of Cost)
- All debris and old sheets to be removed from site within 24 hours
- Structural Steel : JSW / SAIL., VSP / Anchor Bolts: Hilti
- Above All Qty is Approximate, Payment will be based on actual site measurements
- Payment Terms should be enclosed with quotations
- Schedule - 7 to 10 Working Days
- Last date for quotations is 4th June, 2023
- Quotations to delivered at the office of Indian Gymkhana or email to indiangymkhn@yahoo.com
- 5% retention for 6 months will be held back.


Chariman

Projects & Development


President